


**NOTES:**



TIE-IN SCHEDULE			
MARK	SIZE / RATING	ELEVATION	DESCRIPTION
TP-A	4"-150#	-	INLET
TP-B	2"-150#	33 13/16" [858]	GAS OUTLET
TP-C	2"-150#	65 1/8" [1654]	OIL OUTLET
TP-D	2"-150#	15 15/16" [406]	WATER OUT/DRAIN
TP-E	4"-150#	127 3/8" [3235]	V-100 PSV OUT
TP-F	1" NPT	99" [2515]	V-200 PSV OUT
TP-G	1" NPT	42" [1067]	ALT FUEL GAS INLET

NOTE: ALL ELEVATION DIMENSIONS FROM BOTTOM OF SKID.

[illegible]